KOLAR DIVISION.

Notice dated 28th January 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., of 19th February 1929, for restoring Nagadenahalli Hongekere, Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work.	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees two hundred and fifty, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Nagadenahalli-Hongekere, Chintamani Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in figures and words.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for restoring Nagadenahalli-Hongekere Reg. No. 432—450 of Chintamani Taluk:—

No.	Items of work	Per	Quantity	Rate	Cost	Total
	Bund.			Rs.	Rs.	Rs.
1	Earthwork watering and tamping including lead and lift.	C.yds.	4,903			
2 (*a*)	Removing sand at site of puddle wall ...	,,	78			
(*b*)	Puddle wall	,,	20			
3	Turfing ... ,, ,,	Syds.	4,616			
4	Removing and resetting old stone with new jelly.	C.yds.	483			
5	New stone work ... ,,	,,	951			
6	Fixing grade stones including figuring and painting.	No.	22			
7	Fixing B. M. stones including figuring and painting.	,,	2			
8	Fixing Index stones including figuring and painting.	,,	22			
9	Fixing Gauge stone including figuring and painting.	,,	1			
10	Cutting grips and removing ant-hills, etc.	Grades	12			
11	Rooting out trees and clearing jungle, complete.	,,	12			
	Total Bund ...	...	...	...	...	...

No.	Items of work	Per	Quantity	Rate	Cost	Total
				Rs.	Rs.	Rs.
	Sluice.					
1	Earthwork cutting open bund ...	C.yds.	301			
2	Do refilling gap	,,	331			
3	Surki concrete	C.ft.	226			
4	Burnt brick in surki mortar	,,	363			
5	Burnt stone slabs	S.ft.	222			
6	Surki mortar plastering	Sqr.	4·89			
7	Providing plug and rod with locking arrangements.	Lump	sum			
8	Drilling holes in cross and orifice slabs ...	No.	4			
	Total sluice ...	...	...	...	...	...
	Waste Weir.					
1	Earthwork excavation	C.yd.	86			
2	Surki concrete	C.ft.	377			
3	Burnt brick in surki mortar	,,	868			
4	Burnt stone slabs (dressed)	S.ft.	249			
5	Surki mortar plastering	Sqrs.	11·27			
6	New stone work	C.yds.	108			
7	Joggle joints fixing, etc., complete ...	No.	14			
	Total of Weir ...	...	...	...	...	...
	Total of Bund, Sluice and Weir ...	...	...	...	...	...
	Contingencies at 5% ...	...	...	...	...	...
	Grand Total ...	...	...	...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.